



PLANT SCHEDULE

KEY	QTY	SCIENTIFIC NAME	COMMON NAME	SIZE	SPACING	NOTES
DECIDUOUS TREES						
ACE-KAR	6	Acer rubrum 'Karpick'	KARPICK RED MARLE	2'-2.5" CAL	SEE PLAN	
CER-MIN	3	Cercis canadensis 'Minnesota Strain'	MINNESOTA STRAIN REDBLD	8'-10" HT	SEE PLAN	MULTISTEM
GLE-SKY	6	Glendia styracantha 'Skyline'	SKYLINE HONEY LOCUST	7'-3.5" CAL	SEE PLAN	
EVERGREEN SHRUB						
ILE-SHA	14	Ilex glabra 'Shamrock'	SHAMROCK INKBERRY	#5 CONT	6" O.C.	BALLED AND BURLAP
TAX-GRE	12	Taxus x media 'Green Wave'	GREEN WAVE WAVE	18" 24" HT	4" O.C.	BALLED AND BURLAP
DECIDUOUS SHRUBS						
HYD-LIM	3	Hydrangea paniculata 'Limelight'	LIMELIGHT HYDRANGEA	#5 CONT	6" O.C.	
POT-ARB	21	Potentilla fruticosa 'Ablonwood'	ABBOTSWOOD ROSACEAE	#3 CONT	30" O.C.	
RHL-ARO	124	Rhus aromatica 'Gro Low'	GRO LOW SUMAC	#2 CONT	36" O.C.	
ORNAMENTAL GRASSES						
PEN-ALO	94	Pennisetum alopecuroides 'Hamel'	FOUNTAIN GRASS 'HAPELN'	#1 CONT	24" O.C.	
PERENNIALS						
HYL-HER	12	Hymenophyllum 'Herbstfreude'	AUTUMN JOY STONECROP	#1 CONT	24" O.C.	
LEU-BEC	62	Leucantherum superbum 'Becky'	SHASTA DAISY	#1 CONT	24" O.C.	
PER-BLU	85	Perovskia atriplicifolia 'Blue Jean Baby'	BLUE JEAN BABY RUSSIAN SAGE	#1 CONT	18" O.C.	
RUD-GOL	94	Rudbeckia galgula 'Goldstern'	GOLDSTERN BLACK-EYED SUSAN	#1 CONT	18" O.C.	

LEGEND

- CONCRETE SIDEWALK
- ASPHALT PAVING
- STONEDUST PAVING
- GRANITE PAVERS
- LAWN
- PLANTING AREA
- RECLAIMED GRANITE STEPS
- SITE WALL
- EXISTING EDGING
- STEEL TREE TO REMAIN
- PROPOSED DECIDUOUS TREE
- LIGHT OF WORK LINE

PLANTING NOTES

1. All plant material in the plans schedule shall be nursery grown in accordance with ANSI in accordance with Z60.1 Standards for measurement of nursery stock.
2. All plants shall be guaranteed by the Contractor for a period of one year from date of receipt of Provisional Acceptance of the completed installation by the Owner.
3. Replacement plantings will be required prior to Final Acceptance for any plants which are missing, not true to specifications, have died or are unhealthy or uncharacteristic of the species (due to excessive pruning, dieback or other reasons).
4. All plant materials shall be selected and tagged at the nursery by Landscape Architect.
5. The Landscape Architect's approval is required for any plant material substitutions.
6. The Contractor is responsible for immediately notifying the Landscape Architect if any plant quantity discrepancies exist between the planting plan and the plant list.
7. All shrubs and trees will be sprayed with the anti-desiccant 'Wilt-Proof' (or approved equal) prior to the first Winter (no later than November 30).
8. The Landscape Contractor shall have the General Contractor locate all underground utilities in areas to be landscaped prior to commencing any excavation. Adjustments to tree locations will be allowed where utility conflicts are clearly a problem and with prior site approval by Landscape Architect.
9. All plant beds, shrub and tree location shall be staked in the field by Contractor for Landscape Architects approval prior to installation.
10. Adjustments to plant beds shall be approved by Landscape Architect.
11. General Contractor is responsible for all erosion control measures during construction.
12. All disturbed areas are to be topsoiled and seeded or sodded, as indicated in the planting plan.
13. Mulch shall consist of double-shredded hardwood mulch or approved equal and Contractor is responsible for providing samples of mulch to Landscape Architect. Mulch plant materials as shown on plan and details.
14. It is the intent of this contract to avoid any disturbance to existing trees or shrubs on the other than those specifically designated for transplant or removal.
15. Liquidated damages for trees damaged by construction operation shall be \$500 per caliper inch. Shrubs shall be \$100 each.
16. During construction, and until the end of warranty period, existing trees that are showing signs of stress as determined by the Landscape Architect are to be deep root fertilized, two injections per caliper inch tree at 18" - 24" depth with Fertilizer 20-20-20 approved by Landscape Architect.
17. Contractor is responsible for verifying and confirming all plant counts as supplied by the Landscape Architect with field conditions as constructed. Any discrepancies shall be reported to Landscape Architect for approval and direction.
18. Tree transplanting shall be performed by a suitable hydraulic tree spade, sized as necessary to perform the work.
19. Prior to commencement of any construction, all existing trees to remain shall receive tree protection fence at outer edge of drip line whenever possible.



PLEASANTVILLE
VILLAGE OF PLEASANTVILLE
 VILLAGE HALL
 80 WHEELER AVENUE
 WESTCHESTER COUNTY
 VILLAGE OF PLEASANTVILLE, NY 10570
 PHONE: (914) 769-3883
 FAX: (914) 747-3931

WHLA
 WESTCHESTER COUNTY
 LANDSCAPE ARCHITECTURE
Barton & INSIDE
 LANDSCAPE ARCHITECTS P.C.

REVISION NUMBER	DATE	APP'D BY	REVISION

RECORD DRAWING CERTIFICATION

AS BUILT - CHANGES AS NOTED
 AS BUILT - NO CHANGES

CONTRACTOR: _____
 NAME: _____
 SIGNATURE: _____
 TITLE: _____

APPROVED BY THE VILLAGE OF PLEASANTVILLE DEPARTMENT OF PUBLIC WORKS FOR CONSTRUCTION:
 ANTHONY R. CARL, P.E., CEM
 SUPERINTENDENT OF PUBLIC WORKS/VILLAGE ENGINEER
 DATE: _____

MEMORIAL PLAZA CIVIC SPACE
VILLAGE OF PLEASANTVILLE

PLANTING PLAN
 70 MEMORIAL PLAZA,
 VILLAGE OF PLEASANTVILLE, NY 10570

VOP CONTRACT NUMBER: 2024-01
 SHEET NUMBER: L-200
 SHEET NO. 6 OF 23

SCALE: 1"=10'
 DATE: APRIL 19, 2024
 DPW/VILLAGE ENGINEER FILE NO. _____
 REV. 0

CONTRACT DOCUMENTS

ANY ALTERATION OF PLANS, SPECIFICATIONS, PLATS AND REPORTS BEARING THE SEAL OF A LICENSED PROFESSIONAL ENGINEER OR LICENSED LAND SURVEYOR IS A VIOLATION OF SECTION 7209 OF THE NEW YORK STATE EDUCATION LAW, EXCEPT AS PROVIDED FOR BY SECTION 7209, SUBSECTION 2.

IN CHARGE OF: _____ MS
 CHECKED BY: _____ JH
 MADE BY: _____ MS